BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to roads and drains in Amruthahalli and Surroundings in Ward No.07

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. TVenkatesh Gowda S D	
				In figures	In words
1	2707.10	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	225.83	Rupees Two Hundred Twenty Five And Paise Eighty Three Only
2	411.68	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	5687.57	Rupees Five Thousand Six Hundred Eighty Seven And Paise Fifty Seven Only
3	800.78	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	7416.64	Rupees Seven Thousand Four Hundred Sixteen And Paise Sixty Four Only
4	49.66	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500.	MT	77617.86	Rupees Seventy Seven Thousand Six Hundred Seventeen And Paise Eighty Six Only
5	1520.93	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	2451.00	Rupees Two Thousand Four Hundred Fifty One Only
6	651.82	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete, 10 cms thick.	Sqm	1014.00	Rupees One Thousand Fourteen Only
7	651.82	Providing One line dressing to granite stone slab/ granite stone masonry as per speciication	Sqm	997.41	Rupees Nine Hundred Ninety Seven And Paise Forty One Only
8	105.00	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5683.48	Rupees Five Thousand Six Hundred Eighty Three And Paise Forty Eight Only
9		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone